

REQUEST FOR QUOTATION

SLOT 2

	Tender	Description	Qty	Sample/Specs
1.	RFQ758-22	Provision of a contractor for the construction of a palisade fence at Avondale Exchange		Specs attached
2.	RFQ759-22	Provision of a contractor for partitioning of B&E office 9 th floor Runhare House		Specs attached
3.	RFQ760-22	Provision of a contractor for supply and fix Tiling at Mazowe Flats		Specs attached
4.	RFQ761-22	Provision of a contractor for supply and fix tiling at tiling at Borrowdale Exchange		Specs attached
5.	RFQ762-22	Provision of a contractor for the refurbishment of Chimanimani MSAN facilities		Specs attached
6.	RFQ763-22	Supply And Delivery Of Plumbing Materials For Shamva Exchange		Specs attached
7.	RFQ764-22	Provision Of A Contractor For Tilling At Telone Centre For Learning (TCFL)		Specs attached
8.	RFQ765-22	Supply And Delivery Of Plumbing Materials For Bindura Exchange		Specs attached
9.	RFQ766-22	Provision Of A Contractor For Refurbishment Of Victoria Falls Exchange		Specs attached

Requirements

1. Please note that **only** bidders relevant registration with **Procurement Regulatory Authority Of Zimbabwe (PRAZ)** shall be considered.
2. Please attach Proof of PRAZ registration in the specified category
3. Bidders with outstanding works are not eligible.
4. All bids to be priced in local currency (ZW).
5. Bidders should adhere to stated to the delivery periods.

Closing date for ALL Tenders: On or before 1100hrs; Friday 27 May 2022

Your Tender should state the price (Please state your **VAT** status), a firm delivery date and be placed in the tender box on the 8th Floor, South Wing, Runhare House , 107 Kwame Nkrumah Avenue, Harare; OR Emailed to procurement@telone.co.zw

Tel; 264 4 798111; 2902168; Fax 264 4 795499 Runhare House, 107 Kwame Nkrumah Avenue, Harare,



Voice | Broadband | Satellite



RFQ758-22 PROVISION OF A CONTRACTOR FOR THE CONSTRUCTION OF PALISADE FENCE AT AVONDALE

Item	Description	Unit	Quantity	Unit price	Total
SUPPLY AND FIX STEEL SCREEN INSTALLATION					
A	Carefully remove existing precast panel wall and stack at back yard of TelOne Avondale premises, 2.4m height	m	80		
B	Install mild steel screen fence as per attached cross section drawing constructed of square tubes 35x 35x1.2m pickets , 40 x 40 x 1.5mm rails and 100x100x 2mm posts cast in concrete. Hieght from groundlevel to be 2100mm . Please note all dimensions are in millimetres	m	80		
C	5000mm x 2100mm high sliding steel screen gate with pedestrian gate , spiked at the top (as per steel fence members) and painted	No.	2		
D	Paint Prime , undercoat and paint steel screen fence and gates with TelOne colours	Item	1		
	Subtotal				
	Preliminary and General Subtotal				
	VAT				
	Total				

RFQ759-22 PROVISION OF A CONTRACTOR FOR PARTITIONING OF B&E OFFICE 9TH FLOOR

Item	Description	Qty	Unit	Unit Price	Total Price
Fix And Supply					
A	Carefully remove existing suspended ceiling including grid.	18	sqm		
B	Erect full height partition of vinyl (desert sand) clad bison board on natural iodised aluminum H framing. The partition is to be of board 900mm high from floor and 1842mm high 6mm clear glass from top of board to ceiling level. Full partition height is 2742mm. Partition total length is 6000mm,	16.5	sqm		
C	Build-in aluminium single door size 813mm wide x 2100mm high into the front partition. Doors to be complete with locking system and door stops	2	ea		
D	Erect half height partition of vinyl (desert sand) clad bison board on natural iodised aluminum H framing. The partition is to be of board 900mm high from floor and 1100mm high 6mm clear glass from top of board to ceiling level. Full partition height is 2000mm. Partition total length is 4380mm,	2.2	sqm		

E	Install new suspended ceiling at appropriate height for window openings and normal office use with exposed white steel grid and 1500 x 550 acoustic ceiling tiles (Armstrong or similar) for accommodating the ventilation ductwork, and other building systems (e.g. sprinkler system, lighting, etc.) for each office and usable area in accordance with approved standards.	18	sqm		
F	Housekeeping and cleaning	1	Item		

RFQ760-22 PROVISION OF A CONTRACTOR FOR SUPPLY AND FIX MAZOWE TILING

	Description	Qty	Unit
A	Prepare floors to receive floor tiles	190	sqm
B	Prepare walls to receive wall files	40	sqm
C	Install new floor tiles cream ,600mm * 600mm	190	sqm
D	Install new wallfiles white, 150mm* 300mm	40	sqm
E	Touch up and clean the place and dispose rubble off site at an authorised place	1	item

RFQ761-22 PROVISION OF A CONTRACTOR FOR SUPPLY AND FIX TILING AT BORROWDALE EXCHANGE

	Description	Quantity	Unit	Amount
	SUPPLY AND FIX			
A	Prepare floors to receive floor tiles	50	sqm	
B	Install new floor tiles white, 600mm x 600mm incorporating 200mm skirting and proper grouting.	40	sqm	
C	Install new non-slippery floor tiles white at the entrance/verandah, 600mm x 600mm, incorporating 200mm skirting and proper grouting.	10	sqm	
D	Wave blue synthetic polyester vertical curtain blinds, 1500mm high x 1500mm wide	2	ea	
E	Touch up and clean the place and dispose rubble off site at an authorized place	1	Item	

RFQ 762 -22 PROVISION OF A CONTRACTOR FOR THE REFURBISHMENT OF CHIMANIMANI MSAN FACILITIES.

ITEM	DESCRIPTION	QUANTITY	UNIT	Proposed Bidders
1	Carefully remove broken window panes	17	ea	
2	Carefully remove cracked plaster to exterior walls	17	m ²	
3	Carefully existing remove squat WC	1	ea	
	Painting Works: Fix and Supply			
1	Prepare both interior and exterior wall surfaces ton receive paint	355	m ²	
2	Apply new plaster to exterior walls	17	m ²	
3	Apply 1 coat universal undercoat to wall surfaces	355	m ²	

4	Apply 2 coats pva white to interior wall surfaces	250	m ²	
5	Apply 2 coats pva TelOne grey to exterior wall surfaces	105	m ²	
6	Apply pva ceiling white to interior roof surfaces	50	m ²	
7	Apply roof and stoep brilliant blue exterior roof surfaces	50	m ²	
8	Apply 2 coats roof and stoep black to exterior walls skirting	16	m ²	
9	Apply 2 coats gloss enamel white to door/window frames and gutter/down pipe surfaces	20	m ²	
10	Apply gloss enamel grey to door surfaces	34	m ²	
	<u>PLUMBING/SANITARY: Fix and Supply</u>			
	NOTE: ALL PIPES TO BE CHASED IN NOT SURFACE MOUNTED			
1	New Betta Dune Top Flush Toilet Suite, Ceramic, comprising wash down pan with "P" trap and black plastic double flap seat; 9 litre cistern complete with ball valve, siphon and overflow connection, etc. fixed in position to wall, and bedding pan level in cement mortar on floor including jointing to waste pipes and water supply	1	ea	
2	Connect newly installed waste drainage and sewer to existing system	1	Item	
	<u>Glazing: Fix and Supply</u>			
1	Clear glass 460mm x 285mm	6	ea	
2	Clear glass 435mm x 275mm	5	ea	
3	Obscure glass 460mm x 285mm	3	ea	
4	Obscure glass 435mm x 275mm	3	ea	
	<u>Perimeter Fence Painting: Fix and Supply</u>			
	Apply 1 coat silver shine to the perimeter fence, top guard wire and posts measuring 74m (L) x 1.8m (H)	1	item	
	Housekeeping and Cleaning	1	Item	

RFQ763 -22 SUPPLY AND DELIVERY OF PLUMBING MATERIALS FOR SHAMVA EXCHANGE

ITEM	DESCRIPTION	UNIT	QUANTITY	Proposed Bidders
1	Tapes	No	2	
2	40mm saddle pvc	No	1	
3	25mm vsp	No	2	

4	25mm x 6m pipes pvc	No	3	
5	200mls solvent cement	Item	1	
6	15-20mm reducing socket	No	1	
7	15-20mm reducing bush	No	1	
8	15mm G I pipe	No	1	

RFQ764 -22 PROVISION OF A CONTRACTOR FOR TILING AT TELONE CENTRE FOR LEARNING (TCFL)

Works	Description of works	Type	Quantity	Tile size
Tiling of Classrooms	Tiling of 8 classrooms measuring 120m2 each	Ceramic (cream/white)	8	600 x 600mm

RFQ765 -22 SUPPLY AND DELIVERY OF PLUMBING MATERIALS FOR BINDURA EXCHANGE

ITEM	DESCRIPTION	UNIT	QUANTITY	
1	20 mm G.M.S pipes	no	8	
2	20 mm G.M.S plain sockets	no	7	
3	20 mm G.M.S elbows	no	12	
4	20mm G.M.S Tee	no	1	
5	20 mm G.M.S union sockets	no	2	
6	20 mm stop cocks	no	1	
7	20mm G.M.S nipples	no	4	
8	Thread Tap Roll	no	8	

RFQ 766 -22 PROVISION OF A CONTRACTOR FOR REFURBISHMENT OF VICTORIA FALLS EXCHANGE

ITEM	DESCRIPTION	UoM	QTY	RATE	AMOUNT	Proposed Bidders
	<u>VICTORIA FALLS EXCHANGE REFURBISHMENT</u>					
	<u>EXTERNAL WORKS</u>					
	<u>BILL NO. 1</u>					
	<u>PARKING AND PAVING</u>					
	Surface Preparation					
	Remove, scarify and compact the existing tarmac surfaces including the disposal of rubble on to a site to be found by the contractor.	m2	500			
	Antproofing and weedkiller					
A	Approved antproofing and weed killer solution on sand bed under pavings.	m2	500			
	25MPa Mass concrete					
C	Edging between kerb and interlocking	m3	2			
	Finishing top surfaces of concrete with a power float and a coarse hard grass broom					
D	Edging to kerbs etc not exceeding 300mm wide	m2	8			

	60mm Thick 35MPa precast concrete interlocking paving of 100 x 220mm chamfered grey (untinted) paving blocks, laid to falls on and including 20mm thick sand layer with joints filled in with sand, compacted with a vibration compactor.					
E	Paving to parking areas to falls.	m2	500			
	Precast concrete finished smooth on exposed surfaces, including bedding, jointing and pointing					
G	Precast concrete road kerb 150mm wide x 300mm high overall splayed along top of front edge and set in vertical position as described	m	50			
	SURFACE DRAIN					
B	Construct open drain measuring by 400mm wide x 75 mm wide in concrete to match the existing open drain.	m	15			
	Allow for preliminaries and generals					
	Sub-Total					
	Add: VAT		14.50%			
	TOTAL AMOUNT					