

# Request for Quotations

RFQ TENDERS CLOSING 15 AUGUST 2024

Thursday, August 15 · 11:00am

Time zone: UTC

Google Meet joining info

Video call link: <https://meet.google.com/jde-docp-xxb>

Tender	Description	Qty	Specs																																																																																																																																		
1	<p>1125-24</p> <p>Provision of a contractor on a Supply and fix of installation of the refurbishment of TCFL Sewer System</p> <p><b>MANDATORY SITE VISIT</b></p> <table border="1"> <thead> <tr> <th>Item</th> <th>Description</th> <th>Unit</th> <th>Qty</th> <th>Amount</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>TECHNICAL SITE</td> <td></td> <td></td> <td></td> </tr> <tr> <td>a)</td> <td>Demolish existing manholes and prepare the ground for new Manholes</td> <td>sum</td> <td>1</td> <td></td> </tr> <tr> <td>b)</td> <td>Cut down trees</td> <td>no.</td> <td>3</td> <td></td> </tr> <tr> <td>c)</td> <td>Excavate and carefully remove earthen ware 110mm pipes</td> <td>m</td> <td>192</td> <td></td> </tr> <tr> <td>d)</td> <td>Maintain the slope, prepare the trenches, lay and join 160mm pvc pipes complete with 160mm Y-junctions, 10 x 160mm to 110mm Y-junctions, 160mm to 110mm reducer etc</td> <td>6m</td> <td>32</td> <td></td> </tr> <tr> <td>e)</td> <td>Construction of manholes (1200mm x 500mm) complete with fittings, benching and cast iron cover</td> <td>no.</td> <td>4</td> <td></td> </tr> <tr> <td>f)</td> <td>Construction of manhole (1200mm x 1200mm) complete with fittings, benching and cast iron cover</td> <td>no.</td> <td>1</td> <td></td> </tr> <tr> <td>g)</td> <td>Backfilling of trenches</td> <td>m</td> <td>192</td> <td></td> </tr> <tr> <td>h)</td> <td>Clean up the place and make good</td> <td>sum</td> <td>1</td> <td></td> </tr> <tr> <td></td> <td>Sub-total 1</td> <td></td> <td></td> <td></td> </tr> <tr> <td>2</td> <td>CARE TAKER'S HOUSE</td> <td></td> <td></td> <td></td> </tr> <tr> <td>a)</td> <td>Bulk excavation and Construction of a septic tank complete with fittings and cast iron covers</td> <td>no.</td> <td>1</td> <td></td> </tr> <tr> <td>b)</td> <td>Bulk Excavation and Construction of a soak away measuring 3000mm x 2000mm</td> <td>no.</td> <td>1</td> <td></td> </tr> <tr> <td>c)</td> <td>Supply and fix:</td> <td></td> <td></td> <td></td> </tr> <tr> <td>i)</td> <td>110mm PVC pipe</td> <td>6m</td> <td>4</td> <td></td> </tr> <tr> <td>ii)</td> <td>110mm roding eye</td> <td>no.</td> <td>2</td> <td></td> </tr> <tr> <td>iii)</td> <td>110mm PVC 135 Deg bends</td> <td>no.</td> <td>2</td> <td></td> </tr> <tr> <td>iv)</td> <td>110mm PVC Y-junctions</td> <td>no.</td> <td>4</td> <td></td> </tr> <tr> <td>v)</td> <td>110mm gulley head</td> <td>no.</td> <td>1</td> <td></td> </tr> <tr> <td>vi)</td> <td>110mm PVC gulley P trap</td> <td>no.</td> <td>1</td> <td></td> </tr> <tr> <td>d)</td> <td>Build in gully heads, clean up and make Good</td> <td>no.</td> <td>1</td> <td></td> </tr> <tr> <td></td> <td>SUB-TOTAL 2</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>ADD PRELIMINARIES AND GENERALS</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>ADD VAT 15%</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>GRAND TOTAL</td> <td></td> <td></td> <td></td> </tr> </tbody> </table> <p><b>Site visit is on Wednesday 14 August at TCFL 10.00am</b></p>	Item	Description	Unit	Qty	Amount	1	TECHNICAL SITE				a)	Demolish existing manholes and prepare the ground for new Manholes	sum	1		b)	Cut down trees	no.	3		c)	Excavate and carefully remove earthen ware 110mm pipes	m	192		d)	Maintain the slope, prepare the trenches, lay and join 160mm pvc pipes complete with 160mm Y-junctions, 10 x 160mm to 110mm Y-junctions, 160mm to 110mm reducer etc	6m	32		e)	Construction of manholes (1200mm x 500mm) complete with fittings, benching and cast iron cover	no.	4		f)	Construction of manhole (1200mm x 1200mm) complete with fittings, benching and cast iron cover	no.	1		g)	Backfilling of trenches	m	192		h)	Clean up the place and make good	sum	1			Sub-total 1				2	CARE TAKER'S HOUSE				a)	Bulk excavation and Construction of a septic tank complete with fittings and cast iron covers	no.	1		b)	Bulk Excavation and Construction of a soak away measuring 3000mm x 2000mm	no.	1		c)	Supply and fix:				i)	110mm PVC pipe	6m	4		ii)	110mm roding eye	no.	2		iii)	110mm PVC 135 Deg bends	no.	2		iv)	110mm PVC Y-junctions	no.	4		v)	110mm gulley head	no.	1		vi)	110mm PVC gulley P trap	no.	1		d)	Build in gully heads, clean up and make Good	no.	1			SUB-TOTAL 2					ADD PRELIMINARIES AND GENERALS					ADD VAT 15%					GRAND TOTAL					
Item	Description	Unit	Qty	Amount																																																																																																																																	
1	TECHNICAL SITE																																																																																																																																				
a)	Demolish existing manholes and prepare the ground for new Manholes	sum	1																																																																																																																																		
b)	Cut down trees	no.	3																																																																																																																																		
c)	Excavate and carefully remove earthen ware 110mm pipes	m	192																																																																																																																																		
d)	Maintain the slope, prepare the trenches, lay and join 160mm pvc pipes complete with 160mm Y-junctions, 10 x 160mm to 110mm Y-junctions, 160mm to 110mm reducer etc	6m	32																																																																																																																																		
e)	Construction of manholes (1200mm x 500mm) complete with fittings, benching and cast iron cover	no.	4																																																																																																																																		
f)	Construction of manhole (1200mm x 1200mm) complete with fittings, benching and cast iron cover	no.	1																																																																																																																																		
g)	Backfilling of trenches	m	192																																																																																																																																		
h)	Clean up the place and make good	sum	1																																																																																																																																		
	Sub-total 1																																																																																																																																				
2	CARE TAKER'S HOUSE																																																																																																																																				
a)	Bulk excavation and Construction of a septic tank complete with fittings and cast iron covers	no.	1																																																																																																																																		
b)	Bulk Excavation and Construction of a soak away measuring 3000mm x 2000mm	no.	1																																																																																																																																		
c)	Supply and fix:																																																																																																																																				
i)	110mm PVC pipe	6m	4																																																																																																																																		
ii)	110mm roding eye	no.	2																																																																																																																																		
iii)	110mm PVC 135 Deg bends	no.	2																																																																																																																																		
iv)	110mm PVC Y-junctions	no.	4																																																																																																																																		
v)	110mm gulley head	no.	1																																																																																																																																		
vi)	110mm PVC gulley P trap	no.	1																																																																																																																																		
d)	Build in gully heads, clean up and make Good	no.	1																																																																																																																																		
	SUB-TOTAL 2																																																																																																																																				
	ADD PRELIMINARIES AND GENERALS																																																																																																																																				
	ADD VAT 15%																																																																																																																																				
	GRAND TOTAL																																																																																																																																				
2	<p>1126-24</p> <p>Provision of a contractor on a supply and fix basis</p> <p><b>Parehwe Primay School, Mwenezi: Scope of Works/BOQ</b></p> <ul style="list-style-type: none"> <li>• Parehwe Primary School Siting</li> <li>• Parehwe Drilling and casing @ 80m</li> <li>• Capacity Testing</li> <li>• Submersible solar pump and accessories</li> <li>• Steel Stand and Frame 3m x 3m x 2700mm fence, access gate and locking system</li> </ul>																																																																																																																																				

		<ul style="list-style-type: none"> <li>• 4m High Steel Tank Stand</li> <li>• 5000L Jojo Tank</li> <li>• Borehole Connection to Water Tank and Accessories</li> <li>• Inline Chorinator</li> <li>• Lockable Manhole Cover for Pump</li> </ul> <p><b>Perehwe Primary School Mwenezi- 100km away from Mwenezi District Offices</b></p> <ul style="list-style-type: none"> <li>• State the cost of drilling, casing and cabling per metre beyond 8</li> <li>• State the cost of double casing/m</li> <li>• State the cost of steel casing/m</li> <li>• Other compulsory requirements</li> <li>• Inspection of drilling equipment</li> <li>• Delivery period</li> </ul>																																																																																																											
3	1127-24	<p>Provision of a contractor on the assessment of a House, <b>Number 10 Douglas Street, Shurugwi</b> which gutted fire,</p> <ul style="list-style-type: none"> <li>• Perform structural assessment of the burnt building and submit a detailed report with corrective recommendations.</li> <li>• Submit a comprehensive BOQ and scope of works for the necessary repairs to Buildings.</li> <li>•</li> </ul>	1	1																																																																																																									
4	1128-24	<p>Provision of a contractor on a Supply and Fix basis for refurbishment of Bindura Exchange.</p> <table border="1"> <thead> <tr> <th>Item</th> <th>Description</th> <th>Unit</th> <th>Quantity</th> <th>Amount</th> </tr> </thead> <tbody> <tr> <td></td> <td>Preliminaries and Generals</td> <td>sum</td> <td>1</td> <td>\$ -</td> </tr> <tr> <td><b>1</b></td> <td><b>Roof</b></td> <td></td> <td></td> <td></td> </tr> <tr> <td>i</td> <td>Remove and replace IBR roofing sheets measuring 3.6m x 0.8 x0.4mm</td> <td>no</td> <td>10</td> <td>\$</td> </tr> <tr> <td>ii</td> <td>Apply roof sheal to joints on sheets and roofing nails holes</td> <td>m<sup>2</sup></td> <td>20</td> <td>\$</td> </tr> <tr> <td>iii</td> <td>Clean and unblock box gutter and down pipes</td> <td>m</td> <td>200</td> <td>\$</td> </tr> <tr> <td>iv</td> <td>Replace aliminium fascia board with asbestos fascia board (230mm)</td> <td>m</td> <td>140</td> <td>\$</td> </tr> <tr> <td>v</td> <td>Remove damaged ceiling and install new ceiling board ceiling fixed on 38x38mm timbers hanging from roof beams</td> <td>m<sup>2</sup></td> <td>135</td> <td>\$</td> </tr> <tr> <td>iii</td> <td>Clean and prepare ceiling to receive 2 coats of ceiling white Apply 2 coats of PVA ceiling white paint</td> <td>m<sup>2</sup></td> <td>360</td> <td>\$ -</td> </tr> <tr> <td><b>3</b></td> <td><b>Walls</b></td> <td></td> <td></td> <td></td> </tr> <tr> <td>ii</td> <td>Clean and prepare walls to recieve 3 coats of PVA emulsion paint, internally on plaster Apply 1 coat of undercoat paint Apply 2 coats of finishing paint</td> <td>m<sup>2</sup></td> <td>250</td> <td>\$ -</td> </tr> <tr> <td>iii</td> <td>Clean and prepare walls to receive 2 coats of gloss painting internally on painted plaster</td> <td>m<sup>2</sup></td> <td>88</td> <td>\$</td> </tr> <tr> <td><b>5</b></td> <td><b>Doors</b></td> <td></td> <td></td> <td></td> </tr> <tr> <td>i</td> <td>Install new 3 lever locksets</td> <td>no</td> <td>3</td> <td>\$ -</td> </tr> <tr> <td>ii</td> <td>Clean and prepare doors to receive gloss painting</td> <td>no</td> <td>11</td> <td>\$</td> </tr> <tr> <td><b>6</b></td> <td><b>Tiling</b></td> <td></td> <td></td> <td></td> </tr> <tr> <td>i</td> <td>Remove existing floor tiling and prepare floor to receive 330x330mm non slip high traffic ceramic tiles on toilet floor Install on floors as prescribed. Cleaned down on completion</td> <td>m<sup>2</sup></td> <td>106</td> <td>\$ -</td> </tr> <tr> <td>ii</td> <td>Install shiny white wall tiles 200x400mm on walls in abulation facilities</td> <td>m<sup>2</sup></td> <td>80</td> <td>\$ -</td> </tr> <tr> <td><b>7</b></td> <td><b>Glazing</b></td> <td></td> <td></td> <td></td> </tr> <tr> <td>i</td> <td>Replace broken 3mm clear window panes</td> <td>m<sup>2</sup></td> <td>4</td> <td>\$ -</td> </tr> <tr> <td>ii</td> <td>Install a mm OBS window pane</td> <td>m<sup>2</sup></td> <td>6</td> <td>\$ -</td> </tr> </tbody> </table>	Item	Description	Unit	Quantity	Amount		Preliminaries and Generals	sum	1	\$ -	<b>1</b>	<b>Roof</b>				i	Remove and replace IBR roofing sheets measuring 3.6m x 0.8 x0.4mm	no	10	\$	ii	Apply roof sheal to joints on sheets and roofing nails holes	m <sup>2</sup>	20	\$	iii	Clean and unblock box gutter and down pipes	m	200	\$	iv	Replace aliminium fascia board with asbestos fascia board (230mm)	m	140	\$	v	Remove damaged ceiling and install new ceiling board ceiling fixed on 38x38mm timbers hanging from roof beams	m <sup>2</sup>	135	\$	iii	Clean and prepare ceiling to receive 2 coats of ceiling white Apply 2 coats of PVA ceiling white paint	m <sup>2</sup>	360	\$ -	<b>3</b>	<b>Walls</b>				ii	Clean and prepare walls to recieve 3 coats of PVA emulsion paint, internally on plaster Apply 1 coat of undercoat paint Apply 2 coats of finishing paint	m <sup>2</sup>	250	\$ -	iii	Clean and prepare walls to receive 2 coats of gloss painting internally on painted plaster	m <sup>2</sup>	88	\$	<b>5</b>	<b>Doors</b>				i	Install new 3 lever locksets	no	3	\$ -	ii	Clean and prepare doors to receive gloss painting	no	11	\$	<b>6</b>	<b>Tiling</b>				i	Remove existing floor tiling and prepare floor to receive 330x330mm non slip high traffic ceramic tiles on toilet floor Install on floors as prescribed. Cleaned down on completion	m <sup>2</sup>	106	\$ -	ii	Install shiny white wall tiles 200x400mm on walls in abulation facilities	m <sup>2</sup>	80	\$ -	<b>7</b>	<b>Glazing</b>				i	Replace broken 3mm clear window panes	m <sup>2</sup>	4	\$ -	ii	Install a mm OBS window pane	m <sup>2</sup>	6	\$ -		
Item	Description	Unit	Quantity	Amount																																																																																																									
	Preliminaries and Generals	sum	1	\$ -																																																																																																									
<b>1</b>	<b>Roof</b>																																																																																																												
i	Remove and replace IBR roofing sheets measuring 3.6m x 0.8 x0.4mm	no	10	\$																																																																																																									
ii	Apply roof sheal to joints on sheets and roofing nails holes	m <sup>2</sup>	20	\$																																																																																																									
iii	Clean and unblock box gutter and down pipes	m	200	\$																																																																																																									
iv	Replace aliminium fascia board with asbestos fascia board (230mm)	m	140	\$																																																																																																									
v	Remove damaged ceiling and install new ceiling board ceiling fixed on 38x38mm timbers hanging from roof beams	m <sup>2</sup>	135	\$																																																																																																									
iii	Clean and prepare ceiling to receive 2 coats of ceiling white Apply 2 coats of PVA ceiling white paint	m <sup>2</sup>	360	\$ -																																																																																																									
<b>3</b>	<b>Walls</b>																																																																																																												
ii	Clean and prepare walls to recieve 3 coats of PVA emulsion paint, internally on plaster Apply 1 coat of undercoat paint Apply 2 coats of finishing paint	m <sup>2</sup>	250	\$ -																																																																																																									
iii	Clean and prepare walls to receive 2 coats of gloss painting internally on painted plaster	m <sup>2</sup>	88	\$																																																																																																									
<b>5</b>	<b>Doors</b>																																																																																																												
i	Install new 3 lever locksets	no	3	\$ -																																																																																																									
ii	Clean and prepare doors to receive gloss painting	no	11	\$																																																																																																									
<b>6</b>	<b>Tiling</b>																																																																																																												
i	Remove existing floor tiling and prepare floor to receive 330x330mm non slip high traffic ceramic tiles on toilet floor Install on floors as prescribed. Cleaned down on completion	m <sup>2</sup>	106	\$ -																																																																																																									
ii	Install shiny white wall tiles 200x400mm on walls in abulation facilities	m <sup>2</sup>	80	\$ -																																																																																																									
<b>7</b>	<b>Glazing</b>																																																																																																												
i	Replace broken 3mm clear window panes	m <sup>2</sup>	4	\$ -																																																																																																									
ii	Install a mm OBS window pane	m <sup>2</sup>	6	\$ -																																																																																																									

		<b>8</b>	<b>Carpentry</b>					
		i	Remove a broken ceaser stone on kitchen sink measuring 1.5x0.6m	no	1	\$		
		ii	Supply and install a ceaser stone 1.5x0.6mx0.30mm on a sink complete with tap hole	no	1	\$		
		<b>9</b>	<b>Shopfitting</b>					
		i	Aluminium toughened door to receive vinyl frosting pattern to specialist complete with lock and handles					
			Door size 3000x2031mm	no	1	\$	-	
			<b>Sub total</b>			\$	-	
			<b>VAT 15%</b>					
			<b>GRAND TOTAL</b>			\$	-	

5 1129-24 Provision of a contractor on a Supply and Fix basis for refurbishment of TCFL Canteen

Item	Description	Unit	Quantity	Amount
	<b>Canteen Refurbishments at TCFL</b>			
<b>1</b>	<b>Preliminaries and Generals</b>	sum	1	\$ -
<b>2</b>	<b>Tiling Works</b>			
<b>a</b>	<b>Veranda</b>			
<b>i</b>	Prepare floors to receive 600x600mm ceramic tiles.	m <sup>2</sup>	70	\$ -
<b>ii</b>	Install tiles on floors as prescribed. Clean down on completion.			
<b>3</b>	<b>Roof Repairs</b>			
<b>i</b>	Remove existing damaged 9mx1m IBR roof sheets on the canteen roof	no	3	
<b>ii</b>	Supply and fix 9x1m IBR roof sheets and apply roof seal	no	3	\$ -
<b>iii</b>	Remove gutters and keep safe for reinstallation			
<b>iv</b>	Realign asbestos fascia boards measuring 1mx2m and ensure seal	no	20	\$ -
<b>v</b>	Repaint asbestos fascia boards around the canteen building	m <sup>2</sup>	200	\$ -
<b>vi</b>	Carry out cleaning of galvanised box gutter for the canteen building	m	200	\$ -
<b>iv</b>	Finish off gutter cleaning with painting the gutter with gloss white paint and reinstall gutters			
<b>4</b>	<b>Ceiling Repairs</b>			
<b>i</b>	Supply and fix for bison board repairs on canteen ceiling	m <sup>2</sup>	20	\$ -
<b>5</b>	<b>Painting Works</b>			
<b>i</b>	Clean and prepare ceiling to receive 2 coats of ceiling white Apply 2 coats of PVA ceiling white paint	m <sup>2</sup>	350	\$ -
<b>ii</b>	Clean and prepare internal walls to receive 3 coats of gloss paint, on painted walls Apply 1 coat of undercoat paint Apply 2 coats of finishing paint	m <sup>2</sup>	920	\$ -
<b>iii</b>	Clean and prepare external walls to receive 3 coats of PVA	m <sup>2</sup>	480	\$ -

		<p>paint Apply 1 coat of undercoat paint Apply 2 coats of finishing paint</p>						
		<b>Sub total</b>				\$	-	
		<b>VAT 15%</b>						
		<b>GRAND TOTAL</b>				\$	-	
6	1130-24	<p>Supply and delivery of</p> <ul style="list-style-type: none"> <li>• 2.5mm 3 core armored cable</li> <li>• Size 0 gland</li> <li>• Size 0 shroud</li> </ul>					50 2 2	
7	1131-24	<p>Supply and delivery of cell-phones Iphone 15 pro max 256GB Iphone 14 pro max 256GB <b>QUOTE USD PAYABLE IN USD</b></p>					2 1P	
8	1132-24	Supply and delivery of 24 port switches					2	Specification attached
9	1133-24	Supply and delivery of printer heavy duty					1	Specification attached
10	1134.24	<p>Supply and delivery of cartridges:</p> <p>HP59A original TL5120 Black 507S (CE400A) Cyan 507A (CE401A) Magenta 507A (CE403A) Yellow 507a (CE402A) Black 415A (W2030A) Cyan 415A (W2031A) Magenta 415A (2033A) Yellow 415A (2032A) CLT-Y 603L/SEE (Y) CLT-M603/SEE (M) CLT-C603L/SEE (C) CLT-K603L/SEE (K)</p>					2 2 2 2 2 2 1 1 1 1 4 4 4 4	
11	1135-24	<p>Relocation of air conditioning units of TelOne Centre for Learning Site Visit 14 August at 11:00am at TelOne Centre for Learning. <b>Contact Person 0773 471 076</b></p>					3	
12	1136-24	Supply and delivery of danfoss scroll compressors SH184HALC					5	Samples at Apparatus Store Epton Street
13	1137-24	Supply and delivery of core i7 laptop					1	Specification attached
14	1138-24	Supply and delivery of laptops core i7 small screen					4	Specification attached
15	1140-24	Supply and delivery of 3M PVC Trunking 16x25mm packed in 20 or 10 bundles					1000	See sample at Apparatus Store, Epton St.
16	1141-24	Supply and delivery of 9 volts with alkaline energizer					1000	See sample at Apparatus Store, Epton St.
17	1142-24	Supply and delivery of Trunking 3M half moon					500	See sample at Apparatus Store, Epton

				St.
18	1143-24	Supply and delivery of Flat Joint Covers for trunking 40 x 40mm C-Band	100	See sample at Apparatus Store, Epton St.
19	1144-24	Supply and delivery of R410 A Gas	30	See sample at Apparatus Store, Epton St.
20	1145-24	Supply and delivery of Fire Extinguishers dry chemical 2kgs	20	See sample at Transport Stores Epton St.
21	1146-24	Supply and delivery of cross wheel spanner	20	See sample at Transport Stores Epton St.
22	1147-24	Supply and delivery of Mazda BT50 2.2i front hub	6	See sample at Transport Stores Epton St.
23	1148-24	Supply and delivery of Mazda B1800 Brake pads (set)	60 set	See sample at Transport Stores Epton St.
24	1149-24	Supply and delivery of Mazda BT50 2.2 T6 Radiator	6	See sample at Transport Stores Epton St.
25	1150-24	Supply and delivery of Mazda BT50 2.5D Clutch kit	3	See sample at Transport Stores Epton St.
26	1151-24	Supply and delivery of Mazda BT50 2.5D Front wheel bearing	6	See sample at Transport Stores Epton St.
27	1152-24	Supply and delivery of Chevrolet utility overhaul gasket set	30 set	See sample at Transport Stores Epton St.
28	1153-24	Supply and delivery of Chevrolet utility timing belt tensioner	30	See sample at Transport Stores Epton St.
29	1154-24	Supply and delivery of Nissan NP200 Clutch slave	40	See sample at Transport Stores Epton St.
30	1155-24	Supply and delivery of Nissan NP200 Front hubs	30	See sample at Transport Stores Epton

				St.
31	1156-24	Supply and delivery of Nissan NP200 overhaul gasket set	60 set	See sample at Transport Stores Epton St.
32	1157-24	Supply and delivery of Nissan NP200 Radiator fan	20	See sample at Transport Stores Epton St.
33	1158-24	Supply and delivery of Nissan NP200 front shock absorbers	60	See sample at Transport Stores Epton St.
34	1159-24	Supply and delivery of Nissan NP200 : <ul style="list-style-type: none"> <li>• LHS Tail lamp</li> <li>• RHS Tail lamp</li> </ul>	12 12	See sample at Transport Stores Epton St.
35	1160-24	Supply and delivery of Nissan NP200 : <ul style="list-style-type: none"> <li>• LHS Head lamp</li> <li>• RHS Head lamp</li> </ul>	12 12	See sample at Transport Stores Epton St.
36	1161-24	Supply and delivery of Nissan NP200 Brake pads (set)	60 set	See sample at Transport Stores Epton St.
37	1162-24	Supply and delivery of Nissan NP200 wipper blades (set)	200 set	See sample at Transport Stores Epton St.
38	1163-24	Supply and delivery of Nissan NP200: <ul style="list-style-type: none"> <li>• LHS Driveshaft</li> <li>• RHS Drive Shaft</li> </ul>	3 3	See sample at Transport Stores Epton St.

Bidders with outstanding orders for any of the above items will not be considered for supply

TELONE RESERVES THE RIGHT TO INCREASE AND DECREASE QUANTITY

**Closing date for ALL Tenders: On or before 1100hrs; Thursday 15 August 2024**

**Quotations should be in ZiG**

**Payment Terms – 30 days**

Your Tender should state the price (Please state your **VAT** status), a firm delivery date Emailed to [procurement@telone.co.zw](mailto:procurement@telone.co.zw)

- **Bidders should also be compliant with the new regulations for FISCAL TAX INVOICE where necessary.**
- **Each tender should be in its own envelop, tenders should not be**

**mixed on one quotation.**

## SPECIFICATIONS

### RFQ1132-24

Technical Specifications for Cisco C9200L 24 Port Switches

Item #	Item	Description	Quantity
i.	C9200L-24P-4G-E	Catalyst 9200L 24-port PoE+, 4 x 1G, Network Essentials	2
ii.	CON-SNT-C920L24G	SNTC-8X5XNBD Catalyst 9200L 24-port PoE+, 4 x 10G, Net	2
iii.	C9200L-DNA-E-24	C9200L Cisco DNA Essentials, 24-port Term license	2
iv.	C9200L-DNA-E-24-3Y	C9200L Cisco DNA Essentials, 24-port, 3 Year Term license	2
v.	C9200L-NW-E-24	C9200L Network Essentials, 24port license	2
vi.	NETWORK-PNP-LIC	Network Plug-n-Play Connect for zero-touch device deployment	2
vii.	C9K-ACC-RBFT	RUBBER FEET FOR TABLE TOP SETUP 9200 and 9300	2
viii.	C9200-STACK-BLANK	Catalyst 9200 Blank Stack Module	4
ix.	CAB-GUIDE-1RU	1RU CABLE MANAGEMENT GUIDES 9200 and 9300	2
x.	C9K-ACC-SCR-4	12-24 and 10-32 SCREWS FOR RACK INSTALLATION, QTY 4	2
xi.	PWR-C5-BLANK	Config 5 Power Supply Blank	2
xii.	CAB-C15-CBN	Cabinet Jumper Power Cord, 250 VAC 13A, C14-C15 Connectors	2

### RFQ1133-24

#### Heavy Duty Colour LaserJet Managed Multifunction Function Printer

Item	Specification	Compliance
1	Functions	Print, Copy, Scan (fax and wireless)
2	Print speed black (ISO, A4)	55 ppm
3	Print Speed Colour (ISO)	55 ppm
4	First page out black (A4, ready)	As fast as 8 sec
5	First page out colour (A4, ready)	As fast as 10 sec
6	Duplex printing	Automatic (standard)
7	Duty cycle (monthly, letter)	300,000 pages
8	Duty cycle (monthly, A4)	300,000 pages
9	Recommended monthly page volume	50,000 pages
10	Print quality black (best)	Up to 1200 x 1200 dpi, reduced speed to 40 ppm
11	Print quality colour (best)	Up to 1200 x 1200 dpi, reduced speed to 40 ppm
12	Print languages	PCL 5c, PCL 6, Postscript level 3 emulation, PDF (v 1.7), AirPrint™ compatible
13	Print technology	Laser
14	Connectivity, standard	2 Hi-Speed USB 2.0 Host; 1 Hi-Speed USB 2.0 Device; 1 Gigabit Ethernet 10/100/1000T network; 1 Hardware Integration Pocket

15	Mobile printing capability	Yes	
16	Network ready	Standard (built-in Gigabit 10/100/1000T Ethernet)	
17	Network capabilities	Standard (built-in Gigabit 10/100/1000T Ethernet)	
18	Digital sending standard features	Scan to E-mail; Save-to-Network Folder; Save-to-USB drive; Send to Sharepoint; Send to FTP; Send to sFTP; Send to LAN Fax; Send to Internet Fax; Local Address Book; SMTP over SSL; Blank Page Removal; Edge Erase; Auto Colour Sense; Auto Crop To Content; Compact PDF; Auto Tonescale; Auto Orientation; Multi-Pick Detect; Auto Straighten; Auto Crop To Page; OCR	
19	Display	20.3 cm (8.0-in) touchscreen, SVGA Colour Graphic Display (CGD)	
20	Processor speed	1.2 GHz	
21	Memory	8 GB	
22	Internal Storage	500 GB Standard, AES 256 hardware encryption or greater; Secure erase capabilities (Secure File Erase-Temporary Job Files, Secure Erase-Job Data, Secure ATA Erase-Disk).	
23	Compatible Operating Systems	Windows 11; Windows 10; Windows 8; Windows 8.1; Windows 7; Windows Vista; macOS X 10.8 Mountain Lion; macOS X 10.10 Yosemite; Linux; Chrome OS (Full solution software available only for Windows 7 and newer, UPD software available only for Windows 7 and newer.	
24	Paper handling input, standard	100 sheet multi-purpose tray, 2 x 520 sheet input tray, 250 sheet ADF	
25	Paper handling output, standard	500 sheet face-down output bin	
26	Paper handling input, optional	Optional 2,000 sheet tray	
27	Finished output handling	Stapling; Booklet making; Hole punching (with optional output device)	
28	Media types	Plain, Light 60-74g, Bond, Recycled, Mid-Weight 96-110g, Heavy 111-130g, Mid-Weight Glossy 96-110g, Heavy Glossy 111-130g, Extra Heavy Glossy 131-175g, Carstock 176-220g, Card Glossy 176-220g, Light Paperboard 221-255g, Paperboard 256-300g, Heavy Paperboard, Colour Transparency, Labels, Letterhead, Envelope, Heavy Envelope, Preprinted, Prepunched, Coloured	
29	Media sizes supported	Tray 1: A3, A4, A4R, A5, A5R, A6, SRa3, SRA3, Ra4, B4 (JIS), B5 (JIS), B6 (JIS), Oficio, 8K, 16k, Postcard, Dpostcard (JIS), Envelope B5, Envelop C5, Envelope C6, Envelope DL; Tray 2: A4, A4R, A5, A5R, Ra4, B4 (JIS), B5 (JIS), B6(JIS), Oficio, 8K, 16k, Envelope B5, Envelop C5, Envelope C6, Envelope DL; Tray 3: A3, A4, A4R, A5,A5R, Ra3, Ra4, B4 (JIS), B5 (JIS), Oficio, 8K, 16k	
30	Media sizes, custom	Tray 1: 98 x 139.7 to 308 x 457.2 mm; Tray 2: 98 x 139.7 to 297 x 390 mm; Tray 3: 140 x 182 to 320 x 457.2 mm	
31	File Format Supported	CSV; HTML; JPEG; MTIFF; PDF; PDF/A; RTF; TIFF; Text; Unicode Text; XML; XPS	
32	Scanner type	Flatbed, ADF	
33	Scan file format	Digital Send: PDF, Hi-Compression PDF, JPEG, TIFF, MTIFF, XPS, PDF/A, TEXT (OCR), Unicode TEXT (OCR), RTF (OCR), Searchable PDF (OCR), Searchable PDF/A (OCR), HTML (OCR), CSV (OCR); Scan to easy access USB: PDF, JPEG, TIFF, MTIFF, XPS, PDF/A, TEXT (OCR), Unicode TEXT (OCR), RTF (OCR), Searchable PDF (OCR), Searchable PDF/A (OCR), HTML (OCR), CSV (OCR); Print from easy access USB: PDF, PS, Print Ready files (.prn, .pcl, .cht)	
34	Enhanced scanning resolution	Up to 600 x 600 dpi	
35	Scan resolution, optical	Up to 600 x 600 dpi	
36	Scan size (ADF), maximum	109.22 x 1397 mm	
37	Scan size (ADF), minimum	105 x 148 mm	
38	Scan size, maximum	105 x 148 mm	
39	Scan speed (normal, A4)	Up to 120 ppm/240 ipm (black and white); Up to 120 ppm/240 ipm (colour)	
40	Scan speed duplex (normal, A4)	Up to 240 ipm (black and white); Up to 240 ipm (colour)	
41	Automatic document feeder capacity	Standard, 250 sheets	
42	Duplex ADF scanning	Yes	
43	Scan technology	Platen Scanner CCD Digital-CIS	
44	Copy speed (black, normal quality, A4)	Up to 60 cpm	
45	Copy speed (color, normal quality, A4)	Up to 60 cpm	
46	Copy resolution (black text)	Up to 600 x 600 dpi	
47	Copy resolution (color text and graphics)	Up to 600 x 600 dpi	
48	Copy resolution (black graphics)	Up to 600 x 600 dpi	
49	Copies, maximum	Up to 9999 copies	
50	Copy reduce / enlarge settings	25 to 400%	
51	Copier settings	Two-sided copying; Scalability; Image adjustments (darkness, contrast, background cleanup, sharpness); Optimized text/picture (text, mixed, printed picture, photograph); N-Up; N or Z-ordering; Content orientation; Collation; Booklet; ID Scan; Job build; Job	



		storage; Watermark; Stamps; Book mode scans; Erase edges; Automatically detect color/mono; Image preview	
52	Power consumption	1200 watts (printing), 65 watts (ready), 12 watts (sleep), 0.5 watts (auto-off), 0.1 watts (off)	
53	Power	Input voltage: 220 to 240 Vac (+/- 10%), 50/60 Hz (+/- 3 Hz)	
54	Operating humidity range	20 to 80% RH	
55	Recommended operating humidity range	20 to 80% RH	
56	Non-Operating Humidity Range	10 to 80% RH	
57	Operating temperature range	15 to 30°C	
58	Typical electricity consumption (TEC) number	Blue Angel: 4kWh/Week; Energy Star 3.0: 0.984 kWh/Week	
59	Ecolabels	CECP; EPEAT® Gold; ENERGY STAR® qualified	
60	Energy star certified	Yes	
61	Security management	Management security: SNMPv3, SSL/TLS, WPA2-Enterprise, 802.1X authentication (EAP- PEAP, EAP-TLS), IPP over TLS, IPsec/Firewall with Certificate, Pre-Shared Key Authentication, and Kerberos Authentication; Support for WJA-10 IPsec Configuration using IPsec Plug-in	
62	Number of print cartridges	4 (1 each black, cyan, magenta, yellow)	
63	Replacement cartridges to be delivered with printer	Black Managed Toner Cartridge (50,000 pages) Cyan Managed Toner Cartridge (50,000 pages) Yellow Managed Toner Cartridge (50,000 pages) Magenta Managed Toner Cartridge (50,000 pages)	
64	Manufacturer Warranty	1 Year	

## RFQ1137-24

### Core i7 Mgt Laptop Specification

Platform	Windows 11 Pro 64 bit or better
Screen Size	<b>13.5 inches convertible touch screen</b>
Processor Name	Intel® Core™ i7-1255U (up to 4.7 GHz with Intel® Turbo Boost Technology, 12 MB L3 cache, 10 cores, 12 threads)
RAM	16GB DDR4
Storage Capacity	1 TB SSD
Wireless network	Intel® Wi-Fi 6E AX211 (2x2) and Bluetooth® 5.2 combo (Supporting Gigabit data rate)11,121
Networking Options	10/100/1000GB Ethernet
Battery Type	Li-ion
Graphics Memory	4096 GB
Interfaces	Headphone/Microphone Combo, Microphone jack, 2 USB 3.1 Gen 1 (side), 1 RJ-45 (rear), 1 USB 3.1 Gen 1 (rear), 1 HDMI 2.0 (rear), 1 USB 3.1 Type-C(TM) (rear),
Power supply	200-230V AC power adapter
Webcam	HD Webcam (front-facing)
Colour	Nightfall Black
Warranty	1 year limited hardware
Carrying Cases & Sleeves:	Black Leatherette or Nylon padded bag.
Cables & adapters:	1 USB to VGA Adapter, 1 X USB 2.0 Ethernet Adapter, 1 X USB to HDMI (if ports are not available)

## RFQ 1138-24

### Small screen Core i7 General Laptop Specification

Platform	Windows 11 Pro 64 bit
Screen Size	<b>13.5 inches</b>
Processor Name	Core (TM) i7-Processor,10-Core, 12 threads Generation 12 or better

<b>RAM</b>	16GB DDR4/5 expandable to 32Gb
<b>Storage Capacity</b>	1 TB SSD a <b>must</b>
<b>Networking Options</b>	802.11ac (2.4+5.0 GHz Dual-band)
<b>Networking Options</b>	10/100/1000GB Ethernet
<b>Battery Type</b>	Li-ion cell
<b>Graphics Memory</b>	4096 GB
<b>Interfaces</b>	Headphone/Microphone Combo, Microphone jack, 2 USB 3.1 Gen 1 (side), 1 RJ-45 (rear), 1 USB 3.1 Gen 1 (rear), 1 HDMI 2.0 (rear), 1 Mini DisplayPort(TM) (rear), 1 USB 3.1 Type-C(TM) (rear), 1 Media Card Reader <b>or provide adapters</b>
<b>Power supply</b>	200-230V AC power adapter
<b>Webcam</b>	HD Webcam (front-facing)
<b>Colour</b>	Natural silver cover, ash silver keyboard frame
<b>Warranty</b>	1 year limited hardware
<b>Carrying Cases &amp; Sleeves:</b>	Nylon padded backpack (satchel) bag.

No entry level laptops like HP15/HP 250 are allowed