Request for Quotations

ITEM NO	RFQ No.	DESCRIPTION	QTY	SPECIFICATION
1	664-26	**Fix and supply** Replacement of existing underground galvanized pipe 1inch (25mm) with 32mm PVC class 16. Minimum trench depth of 650mm. 1. Plumbing sundries and fittings associated the underground pipe laying task. **Fix and supply** Surface mounted galvanized pipe 1inch (25mm) and branches (20mm and 15mm) with copper pipe (22mm and 15mm). 2. Plumbing sundries and fittings associated the surface pipe laying task e.g. elbows, tees, adaptors and isolation valves. 3. Cutting through the concrete for underground pipe access (50m) and reinstatement of concrete finish of not less than 150mm thickness. 4. Working at heights of 10m for surface mounted pipe replacements. Use of scaffolding recommended. 5. Removal of rubbles from site and disposed accordingly. **MANDATORY SITE VISIT REQUIRED ON MONDAY 24 August 2026 at 11:00AM.** **CONTACT PERSON MR CHIMHUYA 0712 097 551** **CLOSING DATE WEDNESDAY 26 AUGUST 2026 AT 11:00AM**	50m 65m 50m 65m 1	

Closing date for ALL Tenders: On or before 11:00hrs; Wednesday 26 August 2026

Bidding Terms

- **Quotations should be in US$ payable in LOCAL CURRENCY ZWG**
- **Payment Terms – 30 days**
- **Bidders to provide valid tax clearance certificate**
- **Bidders with outstanding orders for any of the above items will not be considered.**
- **TELONE RESERVES THE RIGHT TO INCREASE AND DECREASE QUANTITY**
- **Bidders should also be compliant with the new regulations for FISCAL TAX INVOICE where necessary.**
- **Each tender should be in its own envelope; tenders should not be mixed on one quotation.**
- **It is the Bidder's responsibility to ensure that they receive a receipt confirming submission of their bid that has correct details of the Bidder and the number of the Bid.**

Your Tender should state the price (Please state your VAT status), a firm delivery date Emailed to both procurement@telone.co.zw and procurement@telmail.co.zw. Physical copies to be **HAND DELIVERED** to TelOne, Procurement, 8th Floor, Runhare House.