

Request for Quotations

	Tender	Description	Quantity	Sample/Specs
1.	1181-21	Supply and delivery of roof leaks for CMOC Main Exchange as listed below		
2.	1182-21	Supply and delivery of Epton Street tar resurface as listed below		
3.	1183-21	Hiring of contractor for Highlands Client Services Landscaping maintenance for 1 month		See scope of works below

Please note that **only** bidders registered with **Procurement Regulatory Authority Of Zimbabwe (PRAZ)** shall be considered.

(Please attach Proof of PRAZ registration in the specified category)

Closing date for ALL Tenders: On or before 1100hrs; Friday 26th of November 2021

Your Tender should state the price(Please state your **VAT** status), a firm delivery date and be placed in the tender box on the 8th Floor, South Wing, Runhare House , 107 Kwame Nkrumah Avenue, Harare; OR Emailed to procurement@telone.co.zw

Tel; 264 4 798111; 2902168; Fax 264 4 795499 Runhare House, 107 Kwame Nkrumah Avenue, Harare,



Inquiry No. 1182-21

Ref	Description	Unit	Qty	Rate	Total
	TELONE STORES , EPTOON STREET , HARARE				
	<u>PHASE 1 -ENTRANCE AND EXIT RING ROAD</u>				
	<u>Supply and fix including Plant and Equipment</u>				
A	Pot hole patching : apply gravel,cement stabilizer and asphalt overlay average depth 150mm	sqm	60		

B	Apply overlay thickness 25mm	sqm	900		
C	New tar surfacing to road shoulders	sqm	150		
D	Prepare ground for industrial pavers including laying quarry dust and compacting	sqm	121		
E	Lay industrial concrete pavers including grouting and edging	sqm	121		
F	Road markings to overlaid road	item	1		
		Subtotal			
		VAT			
		Total			

Inquiry No.1181-21

Ref	Description	Quantity	Unit	Amount (ZWL\$)
	<u>Supply and Fix</u>			
A	Carefully prepare suspended floor surfaces to receive new water proofing	796	sqm	
	Level all depressions on the deck surface that may be sources of stagnant water	1	Item	
C	Supply and install to the suspended slab either a two-ply fully reinforced hot rubberized asphalt waterproof membrane slab or an approved torch-on waterproof membrane. All material and application is to be to the satisfaction of TelOne's appointed representative	796	sqm	
	Supply and install a rolled roofing protection sheet over waterproofing membrane. Such protection sheet is to be permanently fastened so it cannot be displaced by weather conditions or by other means.	796	sqm	
	apply the waterproofing membrane 250mm up all suspended slab concrete and/or frame walls and all other up-stands, as may be required.	100	m	
	Supply and install all required miscellaneous metal counter flashings to terminate the waterproofing membrane on concrete walls, stair shaft walls, air shaft walls etc.	1	Item	
	Install the waterproofing membrane	1	Item	

	in accordance with all building codes and/or statutes and manufacturer's recommended specifications			
	Clean up and dispose of all waterproofing material related debris off site in an authorized place	1	Item	

Inquiry No. 1183-21

REF	SCOPE OF WORKS
1.	<ul style="list-style-type: none"> Contractor to provide the necessary manpower, landscaping equipment and tools to ensure gardens and lawn are well maintained at any given time.
2.	<ul style="list-style-type: none"> Contractor shall provide the necessary nutrients to ensure the lawn and flowers are well maintained. Contractor to maintain all rockeries, trimming of trees to improve the scenic of this yard. Contractor to orderly sought any junk network material around the yard i.e. poles and pieces of cables.
3.	<ul style="list-style-type: none"> Contractor shall utilise the same manpower executing cleaning services at this site and proper disposal all material
4.	<ul style="list-style-type: none"> Contractor shall be paid upon satisfactorily work completion form provided by TelOne and signed by user department.